R-15 OSC Plan

Knight Road Community

Cobb County, Georgia

Land Lot 342, 343, & 379, 16th District, 2nd Section

Blake Properties, Inc. prepared for:

north



March 2, 2016 Scale: 1" = 100'



Site Data

10.315 AC 13.015 AC (Less 2.70 AC in floodplain and buffer) Total Site Area: Net Site Area:

Net Density:

Fotal Units Shown:

2.13 UN/AC

(22 units/10.315 AC) Present Zoning:

Minimum Lot Width: **Building Setbacks:** Average Lot Size: Proposed Zoning:

R-15 OSC 10,769 SF

rear:

5' (15' min. between structures) side:

R-15 OSC Density Calculation and Required Open Space

Minimum open space required: 3.90 AC (30%) Open Space provided:

(2.70 AC in floodplain and buffers, 51% of total open space)

Density bonus earned by providing greater than 33% open space. Bonus allows up to 2.25 UN/AC, 2.13 shown on plan.

management and water quality structures are in size and will be revised based on hydrologic study.

Bitean and weitland classifications are to be determined.

No acheological neithretural landmines are known to exist on site.

No utility assembles are known to carried on all such and acheological planeture and acheological planetures are proportionally structures are







Knight

Road



































location map

APPLICANT: Blake Properties, Inc.	PETITION NO:	Z-36
PHONE#: 770-841-9457 EMAIL: bgoodman.bpi@comcast.net	HEARING DATE (PC):	05-03-16
REPRESENTATIVE: Bruce L. Goodman	HEARING DATE (BOC):	05-17-16
PHONE#: 770-841-9457 EMAIL: bgoodman.bpi@comcast.net	PRESENT ZONING:	R-20
TITLEHOLDER: Anthony E. Bentley and Susan P. Bentley; Robert J.		
Van Dyke and R. Lynne Van Dyke; and Peggy Nixon	PROPOSED ZONING:	R-15/OSC
PROPERTY LOCATION: East side of Knight Road, south of		
Blackwell Road	PROPOSED USE:	Subdivision
(3592, 3610 and 3640 Knight Road)		
ACCESS TO PROPERTY: Knight Road	SIZE OF TRACT:	13.015 acres
	DISTRICT:	16
PHYSICAL CHARACTERISTICS TO SITE: Single-family houses	LAND LOT(S):	342, <i>343</i> , 379
and wooded lot	PARCEL(S):	6,7, 5
	TAXES: PAID X D	UE
CONTIGUOUS ZONING/DEVELOPMENT	COMMISSION DISTRICT	: 3

NORTH: R-20/Single-family houses

SOUTH: R-80/Single-family house

EAST: R-20 and R-15/Stockton's Mill

WEST: R-20/Single-family houses and wooded lots

Adjacent Future Land Use:

North: Low Density Residential (LDR) East: Low Density Residential (LDR) South: Low Density Residential (LDR) West: Low Density Residential (LDR)

OPPOSITION: NO. OPPOSED___PETITION NO:___SPOKESMAN ____

PLANNING COMMISSION RECOMMENDATION

APPROVED____MOTION BY____ REJECTED___SECONDED____


HELD____CARRIED____

BOARD OF COMMISSIONERS DECISION

APPROVED____MOTION BY____ REJECTED___SECONDED___ HELD__CARRIED__

| SITE | | Storocharting Way | 343 | | Storocharting Way | 343 | | Storocharting Way | 344 | | Storocharting Way | 345 | Storocharting Way | 345 | | Storocharting Way | 3

STIPULATIONS:



APPLICANT: Blake Properties Inc	PE11110N NO.: <u>Z-36</u>
PRESENT ZONING: R-20	PETITION FOR: R-15/OSC
* * * * * * * * * * * * * * * * * * * *	* * * * * * * * * * * * * * * * * * * *
ZONING COMMENTS: Staff Member Ro	esponsible: Jason A. Campbell
Land Use Plan Recommendation: Low Densi	ty Residential (1-2.5 units per acre)
Proposed Number of Units: 22	Overall Density: 2.13 Units/Acre
	nits* Increase of: 4 Units/Lots taking into account topography, shape of property, utilities, roadways seen circumstances.

Applicant is requesting the R-15 Open Space Community zoning district for the purpose of developing a 22-lot, single-family subdivision. The houses will range in size from 2,200 square feet to 2,500 square feet. The proposed building architecture will be traditional with brick, stone, and hardi-plank. The houses will range in price from the \$400,000s to \$500,000s and up. The Planning Division comments indicate that the OSC requirements have been met. The proposed average lot size is 10,769 square feet and the proposed site plan also indicates there will be 5.33 acres of open space (41% of the total site area).

Cemetery Preservation: No comments.

Site Plan Review: No comment

PPLICANT: Blake Properties Inc		PETITION N	PETITION NO.: Z-36 PETITION FOR: R-15/OSC				
PRESENT ZONING: R-2	PRESENT ZONING: R-20						
**********	******	* * * * * * * * * * * * * * * *	******				
SCHOOL COMMENTS:							
			Number of				
		Capacity	Portable				
Name of School	Enrollment	Status	Classrooms				
Addison	Under						
Elementary							
Simpson	<u>Over</u>						
Middle							
Sprayberry	Under						
Additional Comments:	s are subject to revision at an		*****				

APPLICANT: Blake Properties, Inc	PETITION NO.: Z-36
PRESENT ZONING: R-20	PETITION FOR: R-15/OSC
* * * * * * * * * * * * * * * * * * * *	******
FIRE COMMENTS:	

Modifications may be required to incorporate the Cobb County Fire Marshal's Office comments.

GUEST PARKING: When projects contemplate less than 20 foot separation between units, guest parking shall be provided at a ratio of one-half space for each dwelling unit (1 space/ 2 units).

APPLICANT:	Blake Properties Inc	PETITION NO.: Z-36	
PRESENT ZONIN	NG: R-20	PETITION FOR: R-15/OSC	<u> </u>
* * * * * * * * * * * *	*** ***************	* * * * * * * * * * * * * * * * * *	* * * *
	requesting a rezoning from R-20 with stip 3.015 acre site is located on the east side of Kn		
HB-489 Intergoveri	nmental Agreement Zoning Amendment Notifi	cation:	
Is the application si	te within one half (1/2) mile of a city boundar	y? □ Yes ■ No	
If yes, has the city of	of been notified?	□ Yes ■ No / I	N/A

Comprehensive Plan

The parcel is within a Low Density Residential (LDR) future land use category, with R-20 zoning designations. The purpose of the Low Density Residential (LDR) category is to provide for areas that are suitable for low density housing between one (1) and two and one-half (2.5) dwelling units per acre, and non supportive senior living housing that in certain circumstances may reach five (5) dwelling units per acre, depending on existing conditions such as product type and mix, structure/building height, tract size, topographic conditions, etc in order to provide compatibility with adjacent residential uses.

Specific Area Policy Guidelines:

There are no specific policy guidelines for this area in the Comprehensive Plan.

Adjacent Future Land Use:

North: Low Density Residential (LDR)

East: Low Density Residential (LDR)

South: Low Density Residential (LDR)

West: Low Density Residential (LDR)

Master Plan/Corridor Study

The property is not located within the boundary of a Plan or Corridor Study

Historic Preservation

After consulting various county historic resources surveys, historic maps, archaeology surveys and Civil War trench location maps, staff finds that no known significant historic resources appear to be affected by this application. No further comment. No action by applicant requested at this time.

APPLICANT: Blake Properties Inc	PETITION NO.: _ Z	<u>′</u> -36
PRESENT ZONING: R-20	PETITION FOR: R	k-15/OSC
*********	* * * * * * * * * * * * * * * * * * * *	*****
PLANNING COMMENTS: Continued		
Design Guidelines		
Is the parcel in an area with Design Guidelines? If yes, design guidelines area		
Does the current site plan comply with the design in	equirements?	
<u>Incentive Zones</u>		
Is the property within an Opportunity Zone?	☐ Yes ■ No	
The Opportunity Zone is an incentive that provides	\$3,500 tax credit per job in eligible are	eas if two or more
jobs are being created. This incentive is available f	or new or existing businesses.	
Is the property within an Enterprise Zone?	□ Yes ■ No	
The Enterprise Zone is an incentive	that provides tax abatements and other	economic
incentives for qualifying businesses locating or exp	panding within designated areas for new	jobs and capital
investments.		
Is the property eligible for incentives through the C	Commercial and Industrial Property Reh	abilitation
Program? ☐ Yes	■ No	
The Commercial and Industrial Property Rehabilita	ation Program is an incentive that provi-	des a reduction in
ad valorem property taxes for qualifying redevelop	ment in eligible areas.	
For more information on incentives, please call the	Community Development Agency, Pla	anning Division a
770.528.2018 or find information online at http://e		_
Special Districts		
Is this property within the Cumberland Special Dis	trict #1 (hotel/motel fee)?	
□ Yes ■ No		
Is this property within the Cumberland Special Dis	trict #2 (ad valorem tax)?	
☐ Yes ■ No	arot "2 (ad varotom tax).	
— 100 — 110		

APPLICANT: Blake Properties Inc	PETITION NO.: Z-36
PRESENT ZONING: R-20	PETITION FOR: R-15/OSC
* * * * * * * * * * * * * * * * * * * *	********
PLANNING COMMENTS: Continued	
Is this property within the Six Flags Special Service District?	
☐ Yes ■ No	
Is the property within the Dobbins Airfield Safety Zone?	
☐ Yes ■ No	
If so, which particular safety zone is this property within?	
☐ CZ (Clear Zone) ☐ APZ I (Accident Potential Zone I)
☐ APZ II (Accident Potential Zone II)	
☐ Bird / Wildlife Air Strike Hazard (BASH) area	
OSC Comments:	
Date: March 9, 2016 Contact: Philip Westbrook (770) 528-201	14
Property Location: West of Knight Rd south of Blackwell Rd. Current Zoning: R-20	Land Lot/District: 342, 343, 379 / 16 Proposed Use: R-15 OSC
Total Area: 13.015 acres Floodplain/Wetland Area/Cemetery: 2.70 acres Net Buildable Area: 10.315 acres Base Density Allowed: 2.1 upa Base Density Allowed w/Bonus: 2.25 upa Proposed Lots: 22 Net Density: 2.13 upa Future Land Use: Low Density Residential (1 to 2.5 upa)	
Open Space Requirement: 3.90 acres or 30%; for bonus 4.3 acres Open Space Provided: 5.33 acres or 41% Percentage of Open Space within Floodplain, Wetlands, & Lake	

Setbacks:

Front: 15' Rear: 30'

Side: 5' (15' min. between structures)

APPLICANT:	Blake Prope	rties Inc			P	ETIT	ION	NO.:_	Z-3	36		
PRESENT ZON	NING: R-20				P	ETIT	ION	FOR:	R-1	15/08	SC	
* * * * * * * * *	****	* * * * * * *	* * * * *	****	* * * *	* * * :	* * *	* * * *	* * *	**:	* * *	* *
PLANNING O	COMMENTS:	Continued	i									

Comments:

Development as proposed on site plan received on 03/03/16 does meet the technical requirements of the OSC ordinance and the required percentage of open space that allows a density bonus up to 2.25 units per acre for an R-15 OSC. To further enhance this proposal the following comments and recommendations should be met.

- 1. Overall residential development shall be compatible with neighboring residential uses. Consider modifying exterior lots 1 7 to incorporate larger lot sizes adjacent to existing residential lots.
- 2. Must have Cobb Department of Transportation approved lighting plan in if outdoor lighting (except individual residential lots) is proposed
- 3. A Conservation Easement must be recorded in the mandatory subdivision covenants and with Cobb Superior Court, thereby protecting the "Open Space" from development in perpetuity as owned by the mandatory Home Owners Association. Conservation Easement application must be submitted to the Planning Division before final plat approval.

Recommendations:

- 4. Provide stipulations letter that describes in details the proposed development.
- 5. For all lots contiguous to open space staff recommends including a deed during sale of homes so that future lot owners are aware that commonly owned open space exists adjacent to their property and cannot be built on.
- 6. As another form of privacy barrier staff recommends installing fence (split rail or any fencing compatible with architecture/landscaping/design of development) to the rear of lots that are adjacent to open space
- 7. Provide architectural renderings and description of the façade treatments that will be used on the proposed housing units

Recommend providing site plan that list lot sizes for each lot for compatibility purposes

APPLICANT <u>Blake Properties, Inc.</u>		PETITION NO. $\underline{Z-036}$	
PRESENT ZONING R-20		PETITION FOR R-15/OS	<u>C</u>
* * * * * * * * * * * * * * * * * * * *	* * * * * * * * * *	*************	* *
WATER COMMENTS: NOTE: Comments	reflect only what facil	lities were in existence at the time of this review	w.
Available at Development:	✓ Yes	\square No	
Fire Flow Test Required:	✓ Yes	□ No	
Size / Location of Existing Water Main(s):	6" DI / W side of K	night Road	
Additional Comments:			
Developer may be required to install/upgrade water mains, base Review Process.		•	· *
SEWER COMMENTS: NOTE: Comme	nts reflect only what fa	acilities were in existence at the time of this rev	iew.
In Drainage Basin:	✓ Yes	□ No	
At Development:	✓ Yes	□ No	
Approximate Distance to Nearest Sewer:	On site at SE edge of	of property	
Estimated Waste Generation (in G.P.D.):	A D F= 3,520	Peak= 8,800	
Treatment Plant:	Ν	Noonday	
Plant Capacity:	Available	☐ Not Available	
Line Capacity:	Available	☐ Not Available	
Projected Plant Availability:	✓ 0 - 5 years	s \square 5 - 10 years \square over 10 year	rs
Drv Sewers Required:	☐ Yes	✓ No	
Off-site Easements Required:	✓ Yes*	No *If off-site easements are required, must submit easements to CCWS for	
Flow Test Required:	☐ Yes	✓ No review/approval as to form and stip prior to the execution of easements	oulations
Letter of Allocation issued:	☐ Yes	Property owners. All easement acq are the responsibility of the Develo	uisitions
Septic Tank Recommended by this Departm	ent: Yes	✓ No	
Subject to Health Department Approval:	□ Yes	✓ No	
Additional Sewer on property may be too Gravity flow.	o high. Easement(s)) likely required to Stocktons Mill S/D for	

Developer will be responsible for connecting to the existing County water and sewer systems, installing and/or upgrading all outfalls and water mains, obtaining on and/or offsite easements, dedication of on and/or offsite water and sewer to Cobb County, as may be required. Rezoning does not guarantee water/sewer availability/capacity unless so stated in writing by the Cobb County Water System. Permit issuances subject to continued treatment plant compliance with EPD discharge requirements.

APPLICANT: Blake Properties, Inc.	PETITION NO.: <u>Z-36</u>
PRESENT ZONING: <u>R-20</u>	PETITION FOR: <u>R-15/OSC</u>
* * * * * * * * * * * * * * * * * * * *	* * * * * * * * * * * * * * * * * * * *
STORMWATER MANAGEMENT COMMENTS	
FLOOD HAZARD: YES NO POSSIBLY, NO	OT VERIFIED
DRAINAGE BASIN: Rubes Creek FLOOD HAZAR ☐ FEMA Designated 100 year Floodplain Flood. ☐ Flood Damage Prevention Ordinance DESIGNATED FLOOD Project subject to the Cobb County Flood Damage Prevention Dam Breach zone from (upstream) (onsite) lake - need to keep the company of the cobb county Flood Damage Prevention Dam Breach zone from (upstream) (onsite) lake - need to keep the cobb county Flood Damage Prevention Damage P	OD HAZARD. ion Ordinance Requirements.
WETLANDS: ☐ YES ☐ NO ☐ POSSIBLY, NOT V	ERIFIED
Location: within or adjacent to stream.	
☐ The Owner/Developer is responsible for obtaining any recorns of Engineer.	quired wetland permits from the U.S. Army
STREAMBANK BUFFER ZONE: YES NO P	POSSIBLY, NOT VERIFIED
 Metropolitan River Protection Area (within 2000' of undisturbed buffer each side of waterway). Chattahoochee River Corridor Tributary Area - County revix Georgia Erosion-Sediment Control Law and County Ordina Georgia DNR Variance may be required to work in 25 foot County Buffer Ordinance: 50', 75', 100' or 200' each side of the county Buffer Ordinance: 50', 75', 100' or 200' 	iew (<u>undisturbed</u> buffer each side). ance - County Review/State Review. streambank buffers.
DOWNSTREAM CONDITIONS	
 Potential or Known drainage problems exist for developme Stormwater discharges must be controlled not to exceed the drainage system. Minimize runoff into public roads. 	
 ✓ Minimize the effect of concentrated stormwater discharges ✓ Developer must secure any R.O.W required to receive naturally 	• • •
 Existing Lake Downstream Additional BMP's for erosion sediment controls will be req Lake Study needed to document sediment levels. Stormwater discharges through an established residential needed. Project engineer must evaluate the impact of increased v project on receiving stream. 	eighborhood downstream.

APPLICANT: Blake Properties, Inc.	PETITION NO.: <u>Z-36</u>
PRESENT ZONING: <u>R-20</u>	PETITION FOR: <u>R-15/OSC</u>
* * * * * * * * * * * * * * * * * * * *	* * * * * * * * * * * * * * * * * * * *
STORMWATER MANAGEMENT COMMENTS	S – Continued
SPECIAL SITE CONDITIONS	
 □ Provide comprehensive hydrology/stormwater controls of Submit all proposed site improvements to Plan Review. □ Any spring activity uncovered must be addressed by a condition of the engineer (PE). □ Existing facility. □ Project must comply with the Water Quality require County Water Quality Ordinance. □ Water Quality/Quantity contributions of the existing la conditions into proposed project. □ Calculate and provide % impervious of project site. □ Revisit design; reduce pavement area to reduce runoff and 	qualified geotechnical engineer (PE). In of a qualified registered Georgia geotechnical ements of the CWA-NPDES-NPS Permit and alke/pond on site must be continued as baseline
INSUFFICIENT INFORMATION	
 No Stormwater controls shown Copy of survey is not current – Additional comments mare exposed. No site improvements showing on exhibit. 	nay be forthcoming when current site conditions

ADDITIONAL COMMENTS

- 1. This 13.0 site is located to the east of Knight Road between its intersection with Blackwell Road and Knight Lane. The majority of the site drains to the west directly into the Rubes Creek floodplain. Approximately 3.2 acres of the northwest corner drains to the northwest to the Knight Road right-of-way. The parcel is mostly wooded with slopes ranging from 4% near the road to 35% or greater at the rear adjacent to the creek.
- 2. The proposed Open Space plan appears to keep all of the lot footprints outside the slope areas that exceed 25%.
- 3. A drainage easement may be required at the rear of lots 1-4 to direct runoff directly to the Knight Road right-of-way.

APPLICANT: Blake Properties, Inc.	PETITION NO.: Z-36
PRESENT ZONING: R-20	PETITION FOR: R-15/OSC
* * * * * * * * * * * * * * * * * * * *	* * * * * * * * * * * * * * * * * * * *

TRANSPORTATION COMMENTS:

The following comments and recommendations are based on field investigation and office review of the subject rezoning case:

ROADWAY	AVERAGE DAILY TRIPS	ROADWAY CLASSIFICATION	SPEED LIMIT	JURISDICTIONAL CONTROL	MIN. R.O.W. REQUIREMENTS
Knight Road	800	Minor Collector	30 mph	Cobb County	60'

Based on 2007 traffic counting data taken by Cobb County DOT for Knight Road.

COMMENTS AND OBSERVATIONS

Knight Road is classified as a minor collector and according to the available information the existing right-of-way does not meet the minimum requirements for this classification.

RECOMMENDATIONS

Recommend applicant be required to meet all Cobb County Development Standards and Ordinances related to project improvements.

Recommend applicant consider entering into a development agreement pursuant to O.C.G.A. 36-71-13 for dedication of the following system improvements to mitigate traffic concerns: a) donation of right-of-way on the east side of Knight Road, a minimum of 30' from the roadway centerline.

Recommend a deceleration lane on Knight Road for the entrance.

Recommend curb, gutter, and sidewalk along the Knight Road frontage.

Recommend curb and gutter along both sides and sidewalk along one side of proposed development roadway.

THIS

PAGE

INTENTIONALLY

LEFT

BLANK

STAFF RECOMMENDATIONS

Z-36 BLAKE PROPERTIES, INC.

- A. It is Staff's opinion that the applicant's rezoning proposal may not permit a use that is suitable in view of the use and development of adjacent and nearby properties. Properties on Knight Road are zoned for R-20 and R-80 lots.
- B. It is Staff's opinion that the applicant's rezoning proposal may not have an adverse affect on the usability of adjacent or nearby property. Other properties in the area are zoned for single-family developments that include R-20, R-15 and R-15/OSC, but properties on Knight Road are developed as R-20 and R-80.
- C. It is Staff's opinion that the applicant's rezoning proposal will not result in a use which would cause an excessive or burdensome use of existing streets, transportation facilities, utilities, or schools. This opinion can be supported by the departmental comments contained in this analysis.
- D. It is Staff's opinion that the applicant's rezoning proposal is in conformity with the policy and intent of the *Cobb County Comprehensive Plan*, which delineates this property as being in the Low Density Residential (LDR) land use category for properties having a density ranging from 1-2.5 units per acre. The proposed site plan indicates a net density of 2.13 units per acre. The zoning and densities of some of the other developments in the area include: Stockton's Mill, Unit Four (zoned R-20 at 1.85 units per acre); Ebenezer Farm, Units III & IV (zoned R-20 at 1.89 units per acre); Stockton's Mill (zoned R-15 at 1.95 units per acre); Ebenezer Farm, Unit II (zoned R-15 at 2.14 units per acre); and Churchill Falls, Unit 5A (zoned R-15 at approximately 2.17 units per acre).
- E. It is Staff's opinion that there are existing and changing conditions affecting the use and development of the property which give supporting grounds for deleting the applicant's rezoning proposal to R-20/OSC. Applicant's proposed site plan has set aside 5.33 acres (41%) of the total 13.015 acres as open space. The Planning Division's comments indicate that the OSC requirements have been met. The applicant can receive a density bonus because more than 33% of the property was set aside as open space. The proposed density is within the range for the LDR land use category and is similar to some of the nearby subdivisions. Staff believes developing the property as OSC will leave much more of this site undisturbed than developing the property as R-20.

Based on the above analysis, Staff recommends DELETING to R-20/OSC subject to the following conditions:

- 1. Site plan to be approved by the District Commissioner;
- 2. Lots on the north side of the property are to have rear setbacks of 35 feet;
- 3. Planning Division OSC comments dated March 9, 2016;
- 4. Fire Department comments and recommendations;
- 5. Water and Sewer Division comments and recommendations;
- 6. Stormwater Management Division comments and recommendations;
- 7. Department of Transportation comments and recommendations; and
- 8. Owner/developer to enter into a Development Agreement pursuant to O.C.G.A. §36-71-13 for dedication of system improvements to mitigate traffic concerns.

The recommendations made by the Planning and Zoning Staff are only the opinions of the Planning and Zoning Staff and are by no means the final decision. The Cobb County Board of Commissioners makes the final decisions on all Rezoning and Land Use Permits at an advertised public hearing.



Application No. 2-36 May 2014

Summary of Intent for Rezoning

Part 1.	Resid	ential Rezoning Information (attach additional information if needed)	
	a)	Proposed unit square-footage(s): 2200 - 2500 \$\frac{1}{2}\$.	
	b)	Proposed building architecture: TRADITIONAL BRICK, STONE, HARDY X ANK	
	c)	Proposed selling prices(s): \$ 400 K'S - \$ 500'S ++.	·
	d)	List all requested variances:	
•••••	•••••		
Part 2.	Non-r	residential Rezoning Information (attach additional information if needed)	
	a)	Proposed use(s):	
	b)	Proposed building architecture:	
	c)	Proposed hours/days of operation:	
	d)	List all requested variances:	
		· · · · · · · · · · · · · · · · · · ·	
Part	3. Oth	ner Pertinent Information (List or attach additional information if needed)	
Part 4	. Is an	y of the property included on the proposed site plan owned by the Local, State, or Federal Government?	
		se list all Right-of-Ways, Government owned lots, County owned parcels and/or remnants, etc., and attack	а
	•		•
	рисс	clearly showing where these properties are located).	